

SR #	DWG. NO.	DETAIL NO.	CSI NO	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT LABOR	UNIT MATERIAL	UNIT COST	LABOR SUB TOTAL	MATERIAL SUB TOTAL	TOTAL COST	SUB TOTALS
01 00 00 GENERAL CONDITIONS															
1				Final & Daily Cleanup	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
2				Project Planning, Coordination & Layout	1	0%	1	LS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sub Total															\$ -
09 00 00 FINISHES															
BASEMENT															
CEILING															
3	A2.44	Section B/A6.8		5/8" Type C Gypsum Board Ceiling	351	10%	386	SF	\$ 1.88	\$ 0.85	\$ 2.7	\$ 726	\$ 328	\$ 1,054	
4	A2.44	Section B/A6.8		4x8 Gypsum Board Sheathing	12	0%	12	EA							
5	A2.44	Section B/A6.8		Taping	193	10%	212	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 138	\$ 53	\$ 191	
6	A2.44	Section B/A6.8		Mudding	19	10%	20	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 28	\$ 74	\$ 102	
7	A2.44	Section B/A6.8		Screws	637	0%	637	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 13	\$ 76	\$ 89	
GROUND FLOOR															
GYPSUM BOARD WALL ASSEMBLIES															
8	A2.36 - A2.44	Plan Notes		Wall Type B: Non Rated Partition (15'-8" H)	15	LF	16	H							
9	A2.36 - A2.44	Plan Notes		(1) Layer Of 1/2" Type X Gypsum Board On One Side	230	10%	253	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 397	\$ 152	\$ 549	
10	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	8	0%	8	EA							
11	A2.36 - A2.44	Plan Notes		Taping	126	10%	139	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 90	\$ 35	\$ 125	
12	A2.36 - A2.44	Plan Notes		Mudding	12	10%	13	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 19	\$ 48	\$ 67	
13	A2.36 - A2.44	Plan Notes		Screws	379	0%	379	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 8	\$ 46	\$ 53	
14	A2.36 - A2.44	Plan Notes		Wall Type F: 2 HR Fire Barrier (9'-7" H)	33	LF	10	H							
15	A2.36 - A2.44	Plan Notes		(2) Layer Of 5/8" Type X Gypsum Board On Both Side	1285	10%	1414	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 2,290	\$ 919	\$ 3,209	
16	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	44	0%	44	EA							
17	A2.36 - A2.44	Plan Notes		Taping	707	10%	777	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 505	\$ 194	\$ 700	
18	A2.36 - A2.44	Plan Notes		Mudding	68	10%	75	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 103	\$ 270	\$ 373	
19	A2.36 - A2.44	Plan Notes		Screws	2120	0%	2120	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 42	\$ 254	\$ 297	
20	A2.36 - A2.44	Plan Notes		Wall Type G: 2 HR Fire Barrier (9'-7" H)	15	LF	10	H							
21	A2.36 - A2.44	Plan Notes		(1) Layer Of 5/8" Exterior Gypsum Board Sheathing On One Side	148	10%	163	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 296	\$ 138	\$ 434	
22	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	5	0%	5	EA							
23	A2.36 - A2.44	Plan Notes		Taping	81	10%	89	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 58	\$ 22	\$ 81	
24	A2.36 - A2.44	Plan Notes		Mudding	8	10%	9	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 12	\$ 31	\$ 43	
25	A2.36 - A2.44	Plan Notes		Screws	244	0%	244	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 5	\$ 29	\$ 34	
26	A2.36 - A2.44	Plan Notes		(1) Layer Of 5/8" Gypsum Board On One Side	15	LF	10	H							
27	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	146	10%	161	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 293	\$ 137	\$ 430	
28	A2.36 - A2.44	Plan Notes		Taping	5	0%	5	EA	\$ 0.65	\$ 0.25	\$ 0.9	\$ 4	\$ 1	\$ 5	
29	A2.36 - A2.44	Plan Notes		Mudding	80	10%	88	LF	\$ 1.38	\$ 3.60	\$ 5.0	\$ 122	\$ 319	\$ 441	
30	A2.36 - A2.44	Plan Notes		Screws	8	10%	9	LBS	\$ 0.02	\$ 0.12	\$ 0.1	\$ 0	\$ 1	\$ 1	
31	A2.36 - A2.44	Plan Notes		Wall Type J: 1 HR Rated Partition (10'-0" H)	39	LF	10	H							
32	A2.36 - A2.44	Plan Notes		(1) Layer Of 5/8" Type X Gypsum Board On Both Sides	783	10%	862	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 1,396	\$ 560	\$ 1,956	
33	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	27	0%	27	EA							
34	A2.36 - A2.44	Plan Notes		Taping	431	10%	474	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 308	\$ 118	\$ 426	
35	A2.36 - A2.44	Plan Notes		Mudding	42	10%	46	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 63	\$ 164	\$ 227	
36	A2.36 - A2.44	Plan Notes		Screws	1292	0%	1292	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 26	\$ 155	\$ 181	
37	A2.36 - A2.44	Plan Notes		Wall Type M: 1 HR Rated Infill Wall (9'-7" H)	2	LF	10	H							
38	A2.36 - A2.44	Plan Notes		(2) Layer Of 1/2" Type X Gypsum Board On One Side	45	10%	49	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 77	\$ 29	\$ 107	
39	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	2	0%	2	EA							
40	A2.36 - A2.44	Plan Notes		Taping	25	10%	27	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 18	\$ 7	\$ 24	
41	A2.36 - A2.44	Plan Notes		Mudding	2	10%	3	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 4	\$ 9	\$ 13	
42	A2.36 - A2.44	Plan Notes		Screws	74	0%	74	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 1	\$ 9	\$ 10	
43	A2.36 - A2.44	Plan Notes		Wall Type P: Partition Wall (14'-0" H)	9	LF	14	H							
44	A2.36 - A2.44	Plan Notes		(1) Layer Of 1/2" Gypsum Board On Both Sides	256	10%	282	SF	\$ 1.58	\$ 0.61	\$ 2.2	\$ 445	\$ 172	\$ 617	
45	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	9	0%	9	EA							
46	A2.36 - A2.44	Plan Notes		Taping	141	10%	155	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 101	\$ 39	\$ 139	
47	A2.36 - A2.44	Plan Notes		Mudding	14	10%	15	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 21	\$ 54	\$ 74	
48	A2.36 - A2.44	Plan Notes		Screws	422	0%	422	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 8	\$ 51	\$ 59	
49	A2.36 - A2.44	Plan Notes		Wall Type Q: 1 HR Rated Fire Barrier (8'-0" H)	7	LF	8	H							
50	A2.36 - A2.44	Plan Notes		(1) Layer Of 5/8" Type X Gypsum Board On Both Side	107	10%	118	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 191	\$ 77	\$ 267	
51	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	4	0%	4	EA							
52	A2.36 - A2.44	Plan Notes		Taping	59	10%	65	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 42	\$ 16	\$ 58	
53	A2.36 - A2.44	Plan Notes		Mudding	6	10%	6	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 9	\$ 22	\$ 31	
54	A2.36 - A2.44	Plan Notes		Screws	177	0%	177	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 4	\$ 21	\$ 25	
55	A2.36 - A2.44	Plan Notes		Steel Column Wrap (9'-7" H)	2	LF	10	H							
56	A2.36 - A2.44	Plan Notes		(1) Layer Of 5/8" Type X Gypsum Board On Side	18	10%	20	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 32	\$ 13	\$ 45	
57	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	1	0%	1	EA							
58	A2.36 - A2.44	Plan Notes		Taping	10	10%	11	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 7	\$ 3	\$ 10	
59	A2.36 - A2.44	Plan Notes		Mudding	1	10%	1	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 1	\$ 4	\$ 5	
60	A2.36 - A2.44	Plan Notes		Screws	30	0%	30	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 1	\$ 4	\$ 4	
61	A2.36 - A2.44	Plan Notes		Steel Column Wrap (15'-8" H)	4	LF	16	H							
62	A2.36 - A2.44	Plan Notes		(1) Layer Of 5/8" Type X Gypsum Board On Side	65	10%	71	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 115	\$ 46	\$ 162	
63	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	2	0%	2	EA							
64	A2.36 - A2.44	Plan Notes		Taping	36	10%	39	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 25	\$ 10	\$ 35	
65	A2.36 - A2.44	Plan Notes		Mudding	3	10%	4	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 5	\$ 14	\$ 19	
66	A2.36 - A2.44	Plan Notes		Screws	107	0%	107	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 2	\$ 13	\$ 15	
67	A2.36 - A2.44	Plan Notes		2 HR Rated Column Wrap Type V (10'-0" H)	8	LF	10	H							
68	A2.36 - A2.44	Plan Notes		(2) Layer Of 5/8" Type X Gypsum Board	87	10%	95	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 155	\$ 62	\$ 217	
69	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	3	0%	3	EA							
70	A2.36 - A2.44	Plan Notes		Taping	48	10%	53	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 34	\$ 13	\$ 47	
71	A2.36 - A2.44	Plan Notes		Mudding	5	10%	5	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 7	\$ 18	\$ 25	
72	A2.36 - A2.44	Plan Notes		Screws	143	0%	143	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 3	\$ 17	\$ 20	
73	A2.36 - A2.44	Plan Notes		(1) Layer Of 1/2" Type X Gypsum Board	43	10%	48	SF	\$ 1.58	\$ 0.61	\$ 2.2	\$ 75	\$ 29	\$ 105	
74	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	1	0%	1	EA							
75	A2.36 - A2.44	Plan Notes		Taping	24	10%	26	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 17	\$ 7	\$ 24	
76	A2.36 - A2.44	Plan Notes		Mudding	2	10%	3	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 3	\$ 9	\$ 13	
77	A2.36 - A2.44	Plan Notes		Screws	72	0%	72	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 1	\$ 9	\$ 10	
CEILING															
78	A2.36 - A2.44	Plan Notes		1 HR Rated 1/2" Gypsum Board Ceiling	388	10%	427	SF	\$ 1.85	\$ 0.82	\$ 2.7	\$ 790	\$ 350	\$ 1,140	
79	A2.36 - A2.44	Plan Notes		4x8 Gypsum Board Sheathing	13	0%	13	EA							
80	A2.36 - A2.44	Plan Notes		Taping	213	10%	235	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 153	\$ 59	\$ 211	
81	A2.36 - A2.44	Plan Notes		Mudding	21	10%	23	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$			

91	A2.36 - A2.44	Plan Notes	Mudding	10	10%	11	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 15	\$ 39	\$ 54
92	A2.36 - A2.44	Plan Notes	Screws	336	0%	336	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 7	\$ 40	\$ 47
93	A2.36 - A2.44	Plan Notes	3 Layer 5/8" Type C Exterior Grade Gypsum Board Ceiling	85	10%	94	SF	\$ 2.12	\$ 1.25	\$ 3.4	\$ 199	\$ 117	\$ 316
94	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	3	0%	3	EA						
95	A2.36 - A2.44	Plan Notes	Taping	47	10%	52	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 34	\$ 13	\$ 46
96	A2.36 - A2.44	Plan Notes	Mudding	5	10%	5	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 7	\$ 18	\$ 25
97	A2.36 - A2.44	Plan Notes	Screws	155	0%	155	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 3	\$ 19	\$ 22
FIRST FLOOR													
GYPSUM BOARD WALL ASSEMBLIES													
98	A2.36 - A2.44	Plan Notes	Wall Type B: Non Rated Partition (9'-4" H)	16	LF	9	H						
99	A2.36 - A2.44	Plan Notes	(1) Layer Of 1/2" Type X Gypsum Board On One Side	151	10%	166	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 261	\$ 100	\$ 361
100	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	5	0%	5	EA						
101	A2.36 - A2.44	Plan Notes	Taping	83	10%	92	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 60	\$ 23	\$ 82
102	A2.36 - A2.44	Plan Notes	Mudding	8	10%	9	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 12	\$ 32	\$ 44
103	A2.36 - A2.44	Plan Notes	Screws	250	0%	250	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 5	\$ 30	\$ 35
104	A2.36 - A2.44	Plan Notes	Wall Type F: 2 HR Fire Barrier (12'-10" H)	19	LF	13	H						
105	A2.36 - A2.44	Plan Notes	(2) Layer Of 5/8" Type X Gypsum Board On Both Side	995	10%	1094	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 1,772	\$ 711	\$ 2,483
106	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	34	0%	34	EA						
107	A2.36 - A2.44	Plan Notes	Taping	547	10%	602	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 391	\$ 150	\$ 542
108	A2.36 - A2.44	Plan Notes	Mudding	53	10%	58	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 80	\$ 209	\$ 289
109	A2.36 - A2.44	Plan Notes	Screws	1641	0%	1641	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 33	\$ 197	\$ 230
110	A2.36 - A2.44	Plan Notes	Wall Type K: 2 HR Rated Wall (9'-7" H)	10	LF	10	H						
111	A2.36 - A2.44	Plan Notes	(1) Layer Of 3/4" Type X Gypsum Board On One Side	100	10%	110	SF	\$ 1.70	\$ 0.74	\$ 2.4	\$ 188	\$ 82	\$ 269
112	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	3	0%	3	EA						
113	A2.36 - A2.44	Plan Notes	Taping	55	10%	61	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 39	\$ 15	\$ 55
114	A2.36 - A2.44	Plan Notes	Mudding	5	10%	6	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 8	\$ 21	\$ 29
115	A2.36 - A2.44	Plan Notes	Screws	166	0%	166	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 3	\$ 20	\$ 23
116	A2.36 - A2.44	Plan Notes	Wall Type L: 2 HR Rated Shaft Wall (9'-7" H)	10	LF	10	H						
117	A2.36 - A2.44	Plan Notes	(2) Layer Of 1/2" Type X Gypsum Board On One Side	204	10%	224	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 352	\$ 134	\$ 486
118	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	7	0%	7	EA						
119	A2.36 - A2.44	Plan Notes	Taping	113	10%	123	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 80	\$ 31	\$ 111
120	A2.36 - A2.44	Plan Notes	Mudding	11	10%	12	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 16	\$ 43	\$ 59
121	A2.36 - A2.44	Plan Notes	Screws	336	0%	336	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 7	\$ 40	\$ 47
122	A2.36 - A2.44	Plan Notes	(1) Layer Of 1" Thk Shaftliner Gypsum Board On One Side	10	LF	10	H						
123	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	102	10%	112	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 204	\$ 95	\$ 299
124	A2.36 - A2.44	Plan Notes	Taping	3	0%	3	EA	\$ 0.65	\$ 0.25				
125	A2.36 - A2.44	Plan Notes	Mudding	56	10%	62	LF	\$ 1.38	\$ 3.60	\$ 5.0	\$ 85	\$ 222	\$ 307
126	A2.36 - A2.44	Plan Notes	Screws	5	10%	6	LBS	\$ 0.02	\$ 0.12	\$ 0.1	\$ 0	\$ 1	\$ 1
127	A2.36 - A2.44	Plan Notes	Wall Type N: 2 HR Rated Infill Wall (8'-0" H)	2	LF	8	H						
128	A2.36 - A2.44	Plan Notes	(4) Layer Of 1/2" Type X Gypsum Board On One Side	73	10%	81	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 127	\$ 48	\$ 175
129	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	3	0%	3	EA						
130	A2.36 - A2.44	Plan Notes	Taping	40	10%	44	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 29	\$ 11	\$ 40
131	A2.36 - A2.44	Plan Notes	Mudding	4	10%	4	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 6	\$ 15	\$ 21
132	A2.36 - A2.44	Plan Notes	Screws	121	0%	121	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 2	\$ 15	\$ 17
133	A2.36 - A2.44	Plan Notes	Wall Type Q: 1 HR Rated Fire Barrier (10'-0" H)	13	LF	10	H						
134	A2.36 - A2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On Both Side	252	10%	277	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 449	\$ 180	\$ 630
135	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	9	0%	9	EA						
136	A2.36 - A2.44	Plan Notes	Taping	139	10%	153	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 99	\$ 38	\$ 137
137	A2.36 - A2.44	Plan Notes	Mudding	13	10%	15	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 20	\$ 53	\$ 73
138	A2.36 - A2.44	Plan Notes	Screws	416	0%	416	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 8	\$ 50	\$ 58
139	A2.36 - A2.44	Plan Notes	Steel Column Wrap (9'-7" H)	4	LF	10	H						
140	A2.36 - A2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On Side	39	10%	43	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 69	\$ 28	\$ 97
141	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	1	0%	1	EA						
142	A2.36 - A2.44	Plan Notes	Taping	21	10%	24	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 15	\$ 6	\$ 21
143	A2.36 - A2.44	Plan Notes	Mudding	2	10%	2	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 3	\$ 8	\$ 11
144	A2.36 - A2.44	Plan Notes	Screws	64	0%	64	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 1	\$ 8	\$ 9
CEILING													
145	A2.36 - A2.44	Plan Notes	1 Layer 5/8" Type C Gypsum Board Ceiling	537	10%	591	SF	\$ 1.88	\$ 0.85	\$ 2.7	\$ 1,111	\$ 502	\$ 1,613
146	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	18	0%	18	EA						
147	A2.36 - A2.44	Plan Notes	Taping	295	10%	325	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 211	\$ 81	\$ 292
148	A2.36 - A2.44	Plan Notes	Mudding	28	10%	31	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 43	\$ 113	\$ 156
149	A2.36 - A2.44	Plan Notes	Screws	975	0%	975	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 19	\$ 117	\$ 136
SECOND FLOOR													
GYPSUM BOARD WALL ASSEMBLIES													
150	A2.36 - A2.44	Plan Notes	Wall Type B: Non Rated Partition (11'-8" H)	18	LF	12	H						
151	A2.36 - A2.44	Plan Notes	(1) Layer Of 1/2" Type X Gypsum Board On One Side	207	10%	227	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 357	\$ 136	\$ 493
152	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	7	0%	7	EA						
153	A2.36 - A2.44	Plan Notes	Taping	114	10%	125	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 81	\$ 31	\$ 113
154	A2.36 - A2.44	Plan Notes	Mudding	11	10%	12	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 17	\$ 43	\$ 60
155	A2.36 - A2.44	Plan Notes	Screws	341	0%	341	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 7	\$ 41	\$ 48
156	A2.36 - A2.44	Plan Notes	Wall Type F: 2 HR Fire Barrier (11'-0" H)	13	LF	11	H						
157	A2.36 - A2.44	Plan Notes	(2) Layer Of 5/8" Type X Gypsum Board On Both Side	559	10%	615	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 996	\$ 400	\$ 1,395
158	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	19	0%	19	EA						
159	A2.36 - A2.44	Plan Notes	Taping	307	10%	338	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 220	\$ 85	\$ 304
160	A2.36 - A2.44	Plan Notes	Mudding	30	10%	33	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 45	\$ 117	\$ 162
161	A2.36 - A2.44	Plan Notes	Screws	922	0%	922	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 18	\$ 111	\$ 129
162	A2.36 - A2.44	Plan Notes	Wall Type H: 1 HR Rated Exterior Wall (11'-0" H)	18	LF	11	H						
163	A2.36 - A2.44	Plan Notes	(1) Layer Of 5/8" Exterior Gypsum Board Sheathing On One Side	403	10%	443	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 807	\$ 377	\$ 1,184
164	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	14	0%	14	EA						
165	A2.36 - A2.44	Plan Notes	Taping	222	10%	244	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 158	\$ 61	\$ 219
166	A2.36 - A2.44	Plan Notes	Mudding	21	10%	23	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 32	\$ 85	\$ 117
167	A2.36 - A2.44	Plan Notes	Screws	665	0%	665	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 13	\$ 80	\$ 93
168	A2.36 - A2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On One Side	18	LF	11	H						
169	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	202	10%	222	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 403	\$ 188	\$ 592
170	A2.36 - A2.44	Plan Notes	Taping	7	0%	7	EA	\$ 0.65	\$ 0.25				
171	A2.36 - A2.44	Plan Notes	Mudding	111	10%	122	LF	\$ 1.38	\$ 3.60	\$ 5.0	\$ 168	\$ 439	\$ 607
172	A2.36 - A2.44	Plan Notes	Screws	11	10%	12	LBS	\$ 0.02	\$ 0.12	\$ 0.1	\$ 0	\$ 1	\$ 2
173	A2.36 - A2.44	Plan Notes	Wall Type K: 2 HR Rated Wall (9'-7" H)	6	LF	10	H						
174	A2.36 - A2.44	Plan Notes	(1) Layer Of 3/4" Type X Gypsum Board On One Side	56	10%	62	SF	\$ 1.70	\$ 0.74	\$ 2.4	\$ 105	\$ 46	\$ 150
175	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	2	0%	2	EA						
176	A2.36 - A2.44	Plan Notes	Taping	31	10%	34	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 22	\$ 8	\$ 31
177	A2.36 - A2.44	Plan Notes	Mudding	3	10%	3	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 5	\$ 12	\$ 16
178	A2.36 - A2.44	Plan Notes	Screws	93	0%	93	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 2	\$ 11	\$ 13
179	A2.36 - A2.44	Plan Notes	Wall Type K: 2 HR Rated Wall (11'-8" H)	9	LF	12	H						
180	A2.36 - A2.44	Plan Notes	(1) Layer Of 3/4" Type X Gypsum Board On One Side	110	10%	121	SF	\$ 1.70	\$ 0.74	\$ 2.4	\$ 205	\$ 89	\$ 295
181	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	4	0%	4	EA						
182	A2.36 - A2.44	Plan Notes	Taping	60	10%	66	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 43	\$ 17	\$ 60
183	A2.36 - A2.44	Plan Notes	Mudding	6	10%	6	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 9	\$ 23	\$ 32
184	A2.36 - A2.44	Plan Notes	Screws	181	0%	181	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 4	\$ 22	\$ 25
185	A2.36 - A2.44	Plan Notes	Wall Type L: 2 HR Rated Shaft Wall (11'-0" H)	10	LF	11	H						
186	A2.36 - A2.44	Plan Notes	(2) Layer Of 1/2" Type X Gypsum Board On One Side	230	10%	253	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 397	\$ 152	\$ 548
187	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	8	0%	8	EA						
188	A2.36 - A2.44	Plan Notes	Taping	126	10%	139	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 90	\$ 35	\$ 125
189	A2.36 - A2.44	Plan Notes	Mudding	12	10%	13	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 18	\$ 48	\$ 67
190	A2.36 - A2.44	Plan Notes	Screws	379	0%	379	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 8	\$ 45	\$ 53
191	A2.36 - A2.44	Plan Notes	(1) Layer Of 1" Thk Shaftliner Gypsum Board On One Side	10	LF	11	H						
192	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	115	10%	126	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 230	\$ 107	\$ 337
193	A2.36 - A2.44	Plan Notes	Taping	4	0%	4	EA	\$ 0.65	\$ 0.25				

194	A2.36 - A2.44	Plan Notes	Mudding	63	10%	69	LF	\$ 1.38	\$ 3.60	\$ 5.0	\$ 96	\$ 250	\$ 346
195	A2.36 - A2.44	Plan Notes	Screws	6	10%	7	LBS	\$ 0.02	\$ 0.12	\$ 0.1	\$ 0	\$ 1	\$ 1
196	A2.36 - A2.44	Plan Notes	Wall Type M: 1 HR Rated Infill Wall (9'-7" H)	6	LF	10	H						
197	A2.36 - A2.44	Plan Notes	(2) Layer Of 1/2" Type X Gypsum Board On One Side	114	10%	125	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 197	\$ 75	\$ 272
198	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	4	0%	4	EA						
199	A2.36 - A2.44	Plan Notes	Taping	63	10%	69	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 45	\$ 17	\$ 62
200	A2.36 - A2.44	Plan Notes	Mudding	6	10%	7	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 9	\$ 24	\$ 33
201	A2.36 - A2.44	Plan Notes	Screws	188	0%	188	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 4	\$ 23	\$ 26
202	A2.36 - A2.44	Plan Notes	Wall Type N: 2 HR Rated Infill Wall (8'-0" H)	2	LF	8	H						
203	A2.36 - A2.44	Plan Notes	(4) Layer Of 1/2" Type X Gypsum Board On One Side	73	10%	81	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 127	\$ 48	\$ 175
204	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	3	0%	3	EA						
205	A2.36 - A2.44	Plan Notes	Taping	40	10%	44	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 29	\$ 11	\$ 40
206	A2.36 - A2.44	Plan Notes	Mudding	4	10%	4	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 6	\$ 15	\$ 21
207	A2.36 - A2.44	Plan Notes	Screws	121	0%	121	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 2	\$ 15	\$ 17
208	A2.36 - A2.44	Plan Notes	Wall Type Q: 1 HR Rated Fire Barrier (10'-0" H)	0	LF	10	H						
209	A2.36 - A2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On Both Side	0	10%	0	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ -	\$ -	\$ -
210	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	0	0%	0	EA						
211	A2.36 - A2.44	Plan Notes	Taping	0	10%	0	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ -	\$ -	\$ -
212	A2.36 - A2.44	Plan Notes	Mudding	0	10%	0	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ -	\$ -	\$ -
213	A2.36 - A2.44	Plan Notes	Screws	0	0%	0	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ -	\$ -	\$ -
214	A2.36 - A2.44	Plan Notes	Steel Column Wrap (9'-7" H)	4	LF	10	H						
215	A2.36 - A2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On Side	39	10%	43	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 69	\$ 28	\$ 97
216	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	1	0%	1	EA						
217	A2.36 - A2.44	Plan Notes	Taping	21	10%	24	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 15	\$ 6	\$ 21
218	A2.36 - A2.44	Plan Notes	Mudding	2	10%	2	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 3	\$ 8	\$ 11
219	A2.36 - A2.44	Plan Notes	Screws	64	0%	64	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 1	\$ 8	\$ 9
			CEILING										
220	A2.36 - A2.44	Plan Notes	1 Layer 5/8" Type C Gypsum Board Ceiling	667	10%	734	SF	\$ 1.88	\$ 0.85	\$ 2.7	\$ 1,379	\$ 624	\$ 2,003
221	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	23	0%	23	EA						
222	A2.36 - A2.44	Plan Notes	Taping	367	10%	404	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 262	\$ 101	\$ 363
223	A2.36 - A2.44	Plan Notes	Mudding	35	10%	39	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 54	\$ 140	\$ 194
224	A2.36 - A2.44	Plan Notes	Screws	1211	0%	1211	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 24	\$ 145	\$ 169
			THIRD FLOOR										
			GYPSUM BOARD WALL ASSEMBLIES										
225	A2.36 - A2.44	Plan Notes	Wall Type B: Non Rated Partition (9'-8" H)	22	LF	10	H						
226	A2.36 - A2.44	Plan Notes	(1) Layer Of 1/2" Type X Gypsum Board On One Side	221	10%	243	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 382	\$ 146	\$ 528
227	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	8	0%	8	EA						
228	A2.36 - A2.44	Plan Notes	Taping	122	10%	134	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 87	\$ 33	\$ 120
229	A2.36 - A2.44	Plan Notes	Mudding	12	10%	13	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 18	\$ 46	\$ 64
230	A2.36 - A2.44	Plan Notes	Screws	365	0%	365	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 7	\$ 44	\$ 51
231	A2.36 - A2.44	Plan Notes	Wall Type F: 2 HR Fire Barrier (11'-0" H)	13	LF	11	H						
232	A2.36 - A2.44	Plan Notes	(2) Layer Of 5/8" Type X Gypsum Board On Both Side	559	10%	615	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 996	\$ 400	\$ 1,395
233	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	19	0%	19	EA						
234	A2.36 - A2.44	Plan Notes	Taping	307	10%	338	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 220	\$ 85	\$ 304
235	A2.36 - A2.44	Plan Notes	Mudding	30	10%	33	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 45	\$ 117	\$ 162
236	A2.36 - A2.44	Plan Notes	Screws	922	0%	922	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 18	\$ 111	\$ 129
237	A2.36 - A2.44	Plan Notes	Wall Type H: 1 HR Rated Exterior Wall (11'-0" H)	18	LF	11	H						
238	A2.36 - A2.44	Plan Notes	(1) Layer Of 5/8" Exterior Gypsum Board Sheathing On One Side	403	10%	443	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 807	\$ 377	\$ 1,184
239	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	14	0%	14	EA						
240	A2.36 - A2.44	Plan Notes	Taping	222	10%	244	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 158	\$ 61	\$ 219
241	A2.36 - A2.44	Plan Notes	Mudding	21	10%	23	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 32	\$ 85	\$ 117
242	A2.36 - A2.44	Plan Notes	Screws	665	0%	665	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 13	\$ 80	\$ 93
243	A2.36 - A2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On One Side	18	LF	11	H						
244	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	202	10%	222	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 403	\$ 188	\$ 592
245	A2.36 - A2.44	Plan Notes	Taping	7	0%	7	EA	\$ 0.65	\$ 0.25				
246	A2.36 - A2.44	Plan Notes	Mudding	111	10%	122	LF	\$ 1.38	\$ 3.60	\$ 5.0	\$ 168	\$ 439	\$ 607
247	A2.36 - A2.44	Plan Notes	Screws	11	10%	12	LBS	\$ 0.02	\$ 0.12	\$ 0.1	\$ 0	\$ 1	\$ 2
248	A2.36 - A2.44	Plan Notes	Wall Type K: 2 HR Rated Wall (9'-7" H)	6	LF	10	H						
249	A2.36 - A2.44	Plan Notes	(1) Layer Of 3/4" Type X Gypsum Board On One Side	56	10%	62	SF	\$ 1.70	\$ 0.74	\$ 2.4	\$ 105	\$ 46	\$ 150
250	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	2	0%	2	EA						
251	A2.36 - A2.44	Plan Notes	Taping	31	10%	34	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 22	\$ 8	\$ 31
252	A2.36 - A2.44	Plan Notes	Mudding	3	10%	3	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 5	\$ 12	\$ 16
253	A2.36 - A2.44	Plan Notes	Screws	93	0%	93	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 2	\$ 11	\$ 13
254	A2.36 - A2.44	Plan Notes	Wall Type L: 2 HR Rated Shaft Wall (11'-0" H)	10	LF	11	H						
255	A2.36 - A2.44	Plan Notes	(2) Layer Of 1/2" Type X Gypsum Board On One Side	230	10%	253	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 397	\$ 152	\$ 548
256	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	8	0%	8	EA						
257	A2.36 - A2.44	Plan Notes	Taping	126	10%	139	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 90	\$ 35	\$ 125
258	A2.36 - A2.44	Plan Notes	Mudding	12	10%	13	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 18	\$ 48	\$ 67
259	A2.36 - A2.44	Plan Notes	Screws	379	0%	379	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 8	\$ 45	\$ 53
260	A2.36 - A2.44	Plan Notes	(1) Layer Of 1" Thk Shaftliner Gypsum Board On One Side	10	LF	11	H						
261	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	115	10%	126	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 230	\$ 107	\$ 337
262	A2.36 - A2.44	Plan Notes	Taping	4	0%	4	EA	\$ 0.65	\$ 0.25				
263	A2.36 - A2.44	Plan Notes	Mudding	63	10%	69	LF	\$ 1.38	\$ 3.60	\$ 5.0	\$ 96	\$ 250	\$ 346
264	A2.36 - A2.44	Plan Notes	Screws	6	10%	7	LBS	\$ 0.02	\$ 0.12	\$ 0.1	\$ 0	\$ 1	\$ 1
265	A2.36 - A2.44	Plan Notes	Wall Type M: 1 HR Rated Infill Wall (9'-7" H)	6	LF	10	H						
266	A2.36 - A2.44	Plan Notes	(2) Layer Of 1/2" Type X Gypsum Board On One Side	114	10%	125	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 197	\$ 75	\$ 272
267	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	4	0%	4	EA						
268	A2.36 - A2.44	Plan Notes	Taping	63	10%	69	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 45	\$ 17	\$ 62
269	A2.36 - A2.44	Plan Notes	Mudding	6	10%	7	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 9	\$ 24	\$ 33
270	A2.36 - A2.44	Plan Notes	Screws	188	0%	188	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 4	\$ 23	\$ 26
271	A2.36 - A2.44	Plan Notes	Wall Type N: 2 HR Rated Infill Wall (8'-0" H)	2	LF	8	H						
272	A2.36 - A2.44	Plan Notes	(4) Layer Of 1/2" Type X Gypsum Board On One Side	73	10%	81	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 127	\$ 48	\$ 175
273	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	3	0%	3	EA						
274	A2.36 - A2.44	Plan Notes	Taping	40	10%	44	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 29	\$ 11	\$ 40
275	A2.36 - A2.44	Plan Notes	Mudding	4	10%	4	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 6	\$ 15	\$ 21
276	A2.36 - A2.44	Plan Notes	Screws	121	0%	121	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 2	\$ 15	\$ 17
277	A2.36 - A2.44	Plan Notes	Wall Type P: Partition Wall (9'-8" H)	2	LF	10	H						
278	A2.36 - A2.44	Plan Notes	(1) Layer Of 1/2" Gypsum Board On Both Sides	45	10%	49	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 77	\$ 29	\$ 106
279	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	2	0%	2	EA						
280	A2.36 - A2.44	Plan Notes	Taping	25	10%	27	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 18	\$ 7	\$ 24
281	A2.36 - A2.44	Plan Notes	Mudding	2	10%	3	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 4	\$ 9	\$ 13
282	A2.36 - A2.44	Plan Notes	Screws	74	0%	74	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 1	\$ 9	\$ 10
283	A2.36 - A2.44	Plan Notes	Steel Column Wrap (9'-7" H)	4	LF	10	H						
284	A2.36 - A2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On Side	39	10%	43	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 69	\$ 28	\$ 97
285	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	1	0%	1	EA						
286	A2.36 - A2.44	Plan Notes	Taping	21	10%	24	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 15	\$ 6	\$ 21
287	A2.36 - A2.44	Plan Notes	Mudding	2	10%	2	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 3	\$ 8	\$ 11
288	A2.36 - A2.44	Plan Notes	Screws	64	0%	64	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 1	\$ 8	\$ 9
			CEILING										
289	A2.36 - A2.44	Plan Notes	1 Layer 5/8" Type C Gypsum Board Ceiling	440	10%	484	SF	\$ 1.88	\$ 0.85	\$ 2.7	\$ 910	\$ 411	\$ 1,321
290	A2.36 - A2.44	Plan Notes	4x8 Gypsum Board Sheathing	15	0%	15	EA						
291	A2.36 - A2.44	Plan Notes	Taping	242	10%	266	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 173	\$ 67	\$ 240
292	A2.36 - A2.44	Plan Notes	Mudding	23	10%	26	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 35	\$ 92	\$ 128
293	A2.36 - A2.44	Plan Notes	Screws	798	0%	798	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 16	\$ 96	\$ 112
			FOURTH FLOOR										
			GYPSUM BOARD WALL ASSEMBLIES										
294	A.2.37 - 2.44	Plan Notes	Wall Type B: Non Rated Partition (9'-7" H)	25	LF	10	H						
295	A.2.37 -												

400	A.2.37 - 2.44	Plan Notes	Taping	224	10%	247	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 160	\$ 62	\$ 222
401	A.2.37 - 2.44	Plan Notes	Mudding	22	10%	24	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 33	\$ 86	\$ 118
402	A.2.37 - 2.44	Plan Notes	Screws	740	0%	740	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 15	\$ 89	\$ 104
403	A.2.37 - 2.44	Plan Notes	5/8" Type C Gypsum Board Ceiling	238	10%	262	SF	\$ 1.88	\$ 0.85	\$ 2.7	\$ 493	\$ 223	\$ 715
404	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	8	0%	8	EA						
405	A.2.37 - 2.44	Plan Notes	Taping	131	10%	144	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 94	\$ 36	\$ 130
406	A.2.37 - 2.44	Plan Notes	Mudding	13	10%	14	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 19	\$ 50	\$ 69
407	A.2.37 - 2.44	Plan Notes	Screws	432	0%	432	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 9	\$ 52	\$ 61
SIXTH FLOOR													
GYPSUM BOARD WALL ASSEMBLIES													
408	A.2.37 - 2.44	Plan Notes	Wall Type B: Non Rated Partition (10'-10" H)	25	LF	11	H						
409	A.2.37 - 2.44	Plan Notes	(1) Layer Of 1/2" Type X Gypsum Board On One Side	265	10%	292	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 458	\$ 175	\$ 633
410	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	9	0%	9	EA						
411	A.2.37 - 2.44	Plan Notes	Taping	146	10%	161	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 104	\$ 40	\$ 144
412	A.2.37 - 2.44	Plan Notes	Mudding	14	10%	15	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 21	\$ 56	\$ 77
413	A.2.37 - 2.44	Plan Notes	Screws	438	0%	438	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 9	\$ 53	\$ 61
414	A.2.37 - 2.44	Plan Notes	Wall Type L: 2 HR Rated Shaft Wall (10'-10" H)	10	LF	11	H						
415	A.2.37 - 2.44	Plan Notes	(2) Layer Of 1/2" Type X Gypsum Board On One Side	226	10%	249	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 391	\$ 149	\$ 540
416	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	8	0%	8	EA						
417	A.2.37 - 2.44	Plan Notes	Taping	124	10%	137	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 89	\$ 34	\$ 123
418	A.2.37 - 2.44	Plan Notes	Mudding	12	10%	13	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 18	\$ 47	\$ 56
419	A.2.37 - 2.44	Plan Notes	Screws	373	0%	373	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 7	\$ 45	\$ 62
420	A.2.37 - 2.44	Plan Notes	(1) Layer Of 1" Thk Shaftliner Gypsum Board On One Side	10	LF	11	H						
421	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	113	10%	124	SF	\$ 1.82	\$ 0.85	\$ 2.7	\$ 226	\$ 106	\$ 332
422	A.2.37 - 2.44	Plan Notes	Taping	4	0%	4	EA	\$ 0.65	\$ 0.25				
423	A.2.37 - 2.44	Plan Notes	Mudding	62	10%	68	LF	\$ 1.38	\$ 3.60	\$ 5.0	\$ 94	\$ 246	\$ 341
424	A.2.37 - 2.44	Plan Notes	Screws	6	10%	7	LBS	\$ 0.02	\$ 0.12	\$ 0.1	\$ 0	\$ 1	\$ 1
425	A.2.37 - 2.44	Plan Notes	Wall Type F: 2 HR Fire Barrier (10'-10" H)	8	LF	11	H						
426	A.2.37 - 2.44	Plan Notes	(2) Layer Of 5/8" Type X Gypsum Board On Both Side	344	10%	378	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 613	\$ 246	\$ 859
427	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	12	0%	12	EA						
428	A.2.37 - 2.44	Plan Notes	Taping	189	10%	208	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 135	\$ 52	\$ 187
429	A.2.37 - 2.44	Plan Notes	Mudding	18	10%	20	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 28	\$ 72	\$ 100
430	A.2.37 - 2.44	Plan Notes	Screws	568	0%	568	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 11	\$ 68	\$ 79
431	A.2.37 - 2.44	Plan Notes	Wall Type M: 1 HR Rated Infill Wall (10'-10" H)	11	LF	11	H						
432	A.2.37 - 2.44	Plan Notes	(2) Layer Of 1/2" Type X Gypsum Board On One Side	248	10%	272	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 428	\$ 163	\$ 591
433	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	9	0%	9	EA						
434	A.2.37 - 2.44	Plan Notes	Taping	136	10%	150	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 97	\$ 37	\$ 135
435	A.2.37 - 2.44	Plan Notes	Mudding	13	10%	14	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 20	\$ 52	\$ 72
436	A.2.37 - 2.44	Plan Notes	Screws	408	0%	408	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 8	\$ 49	\$ 57
437	A.2.37 - 2.44	Plan Notes	Wall Type K: 2 HR Rated Wall (10'-10" H)	6	LF	11	H						
438	A.2.37 - 2.44	Plan Notes	(1) Layer Of 3/4" Type X Gypsum Board On One Side	63	10%	70	SF	\$ 1.70	\$ 0.74	\$ 2.4	\$ 118	\$ 51	\$ 170
439	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	2	0%	2	EA						
440	A.2.37 - 2.44	Plan Notes	Taping	35	10%	38	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 25	\$ 10	\$ 34
441	A.2.37 - 2.44	Plan Notes	Mudding	3	10%	4	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 5	\$ 13	\$ 18
442	A.2.37 - 2.44	Plan Notes	Screws	104	0%	104	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 2	\$ 13	\$ 15
443	A.2.37 - 2.44	Plan Notes	Wall Type Q: 1 HR Rated Fire Barrier (10'-10" H)	5	LF	11	H						
444	A.2.37 - 2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On Both Side	103	10%	113	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 183	\$ 74	\$ 257
445	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	4	0%	4	EA						
446	A.2.37 - 2.44	Plan Notes	Taping	57	10%	62	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 40	\$ 16	\$ 56
447	A.2.37 - 2.44	Plan Notes	Mudding	5	10%	6	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 8	\$ 22	\$ 30
448	A.2.37 - 2.44	Plan Notes	Screws	170	0%	170	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 3	\$ 20	\$ 24
449	A.2.37 - 2.44	Plan Notes	Column Wrap (10'-10" H)	4	LF	11	H						
450	A.2.37 - 2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On Side	48	10%	52	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 85	\$ 34	\$ 119
451	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	2	0%	2	EA						
452	A.2.37 - 2.44	Plan Notes	Taping	26	10%	29	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 19	\$ 7	\$ 26
453	A.2.37 - 2.44	Plan Notes	Mudding	3	10%	3	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 4	\$ 10	\$ 14
454	A.2.37 - 2.44	Plan Notes	Screws	79	0%	79	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 2	\$ 9	\$ 11
CEILING													
455	A.2.37 - 2.44	Plan Notes	1 HR Rated 1/2" Gypsum Board Ceiling	408	10%	449	SF	\$ 1.85	\$ 0.82	\$ 2.7	\$ 830	\$ 368	\$ 1,198
456	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	14	0%	14	EA						
457	A.2.37 - 2.44	Plan Notes	Taping	224	10%	247	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 160	\$ 62	\$ 222
458	A.2.37 - 2.44	Plan Notes	Mudding	22	10%	24	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 33	\$ 86	\$ 118
459	A.2.37 - 2.44	Plan Notes	Screws	741	0%	741	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 15	\$ 89	\$ 104
460	A.2.37 - 2.44	Plan Notes	5/8" Type C Gypsum Board Ceiling	349	10%	384	SF	\$ 1.88	\$ 0.85	\$ 2.7	\$ 721	\$ 326	\$ 1,047
461	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	12	0%	12	EA						
462	A.2.37 - 2.44	Plan Notes	Taping	192	10%	211	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 137	\$ 53	\$ 190
463	A.2.37 - 2.44	Plan Notes	Mudding	18	10%	20	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 28	\$ 73	\$ 101
464	A.2.37 - 2.44	Plan Notes	Screws	633	0%	633	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 13	\$ 76	\$ 89
SEVENTH FLOOR													
GYPSUM BOARD WALL ASSEMBLIES													
465	A.2.37 - 2.44	Plan Notes	Wall Type B: Non Rated Partition (10'-10" H)	26	LF	11	H						
466	A.2.37 - 2.44	Plan Notes	(1) Layer Of 1/2" Type X Gypsum Board On One Side	279	10%	307	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 482	\$ 184	\$ 667
467	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	10	0%	10	EA						
468	A.2.37 - 2.44	Plan Notes	Taping	154	10%	169	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 110	\$ 42	\$ 152
469	A.2.37 - 2.44	Plan Notes	Mudding	15	10%	16	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 22	\$ 59	\$ 81
470	A.2.37 - 2.44	Plan Notes	Screws	461	0%	461	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 9	\$ 55	\$ 65
471	A.2.37 - 2.44	Plan Notes	Wall Type L: 2 HR Rated Shaft Wall (10'-10" H)	10	LF	11	H						
472	A.2.37 - 2.44	Plan Notes	(2) Layer Of 1/2" Type X Gypsum Board On One Side	226	10%	249	SF	\$ 1.57	\$ 0.60	\$ 2.2	\$ 391	\$ 149	\$ 540
473	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	8	0%	8	EA						
474	A.2.37 - 2.44	Plan Notes	Taping	124	10%	137	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 89	\$ 34	\$ 123
475	A.2.37 - 2.44	Plan Notes	Mudding	12	10%	13	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 18	\$ 47	\$ 56
476	A.2.37 - 2.44	Plan Notes	Screws	373	0%	373	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 7	\$ 45	\$ 52
477	A.2.37 - 2.44	Plan Notes	Wall Type L: 2 HR Rated Shaft Wall (10'-10" H)	10	LF	11	H						
478	A.2.37 - 2.44	Plan Notes	(1) Layer Of 1" Thk Shaftliner Gypsum Board On One Side	113	10%	124	SF	\$ 1.89	\$ 0.92	\$ 2.8	\$ 235	\$ 114	\$ 349
479	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	4	0%	4	EA						
480	A.2.37 - 2.44	Plan Notes	Taping	62	10%	68	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 44	\$ 17	\$ 62
481	A.2.37 - 2.44	Plan Notes	Mudding	6	10%	7	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 9	\$ 24	\$ 33
482	A.2.37 - 2.44	Plan Notes	Screws	187	0%	187	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 4	\$ 22	\$ 26
483	A.2.37 - 2.44	Plan Notes	Wall Type H: 1 HR Exterior Rated Wall (10'-10" H)	24	LF	11	H						
484	A.2.37 - 2.44	Plan Notes	(1) Layer Of 5/8" Type X Gypsum Board On One Side	265	10%	292	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 473	\$ 190	\$ 662
485	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	9	0%	9	EA						
486	A.2.37 - 2.44	Plan Notes	Taping	146	10%	160	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 104	\$ 40	\$ 144
487	A.2.37 - 2.44	Plan Notes	Mudding	14	10%	15	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 21	\$ 56	\$ 77
488	A.2.37 - 2.44	Plan Notes	Screws	438	0%	438	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 9	\$ 53	\$ 61
489	A.2.37 - 2.44	Plan Notes	Wall Type F: 2 HR Fire Barrier (10'-10" H)	8	LF	11	H						
490	A.2.37 - 2.44	Plan Notes	(2) Layer Of 5/8" EXT Gypsum Board Sheathing On One Side	344	10%	378	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 613	\$ 246	\$ 859
491	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	9	0%	9	EA						
492	A.2.37 - 2.44	Plan Notes	Taping	146	10%	160	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 104	\$ 40	\$ 144
493	A.2.37 - 2.44	Plan Notes	Mudding	14	10%	15	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 21	\$ 56	\$ 77
494	A.2.37 - 2.44	Plan Notes	Screws	438	0%	438	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 9	\$ 53	\$ 61
495	A.2.37 - 2.44	Plan Notes	Wall Type F: 2 HR Fire Barrier (10'-10" H)	8	LF	11	H						
496	A.2.37 - 2.44	Plan Notes	(2) Layer Of 5/8" Type X Gypsum Board On Both Side	344	10%	378	SF	\$ 1.62	\$ 0.65	\$ 2.3	\$ 613	\$ 246	\$ 859
497	A.2.37 - 2.44	Plan Notes	4x8 Gypsum Board Sheathing	12	0%	12	EA						
498	A.2.37 - 2.44	Plan Notes	Taping	189	10%	208	LF	\$ 0.65	\$ 0.25	\$ 0.9	\$ 135	\$ 52	\$ 187
499	A.2.37 - 2.44	Plan Notes	Mudding	18	10%	20	LBS	\$ 1.38	\$ 3.60	\$ 5.0	\$ 28	\$ 72	\$ 100
500	A.2.37 - 2.44	Plan Notes	Screws	568	0%	568	EA	\$ 0.02	\$ 0.12	\$ 0.1	\$ 11	\$ 68	\$ 79
501	A.2.37 - 2.44	Plan Notes	Wall Type M: 1 HR Rated Infill Wall (10'-10" H)	11	LF	11	H						

